

Sidewalk Summary

DRAFT June 28, 2017

Village of Hyde Park

<u>Road Name, Section</u>	<u>Side</u>	<u>Existing Type</u>	<u>Length (ft)</u>	<u>Condition</u>	<u>Installed</u>	<u>Estimated Cost for New</u>	<u>Notes</u>
Church Street, Main to Post Office	East	Paved	550	Poor	unknown	\$ 220,000	Narrow, non-ADA, painted walkway on east side
Church Street, Main St to Post Office	West	Paved	300	Fair	unknown	\$ 120,000	Narrow, non-ADA
Church Street, Post Office to Rt 15	East	Concrete	900	N/A	planning only	\$ 360,000	Benefits from roundabout Bike/Ped reconstruction
Main Street, West Main to Depot	North	Concrete	1,500	Mixed	1991-1998 & 2003	\$ 600,000	Some paved sections, crosswalks poor condition
Main Street, West Main to Depot	South	Concrete	1,500	Fair	1987	\$ 600,000	Needs repair in sections, spalling due to salt
Main Street, Courthouse Ramp	South	Concrete	45	Good	2016	\$ 18,000	May need modification for crosswalk
Eden Street, start at Main St	West	Paved	900	Fair	unknown	\$ 360,000	Narrow, non-ADA
West Main Street, start at Main St	North	Paved	450	Poor	unknown	\$ 180,000	Needs replacement; undefined at parish hall
West Main Street, start at Main St	South	Paved	250	Poor	unknown	\$ 100,000	Needs replacement; merges with paved road
West Main Street, from end of paved ro:	North	Gravel	1,100	N/A	planning only	\$ 440,000	New path / wide shoulder to access LVRT
East Main Street, start at Main St	South	Concrete	125	Good	2015	\$ 50,000	Access to school parking lot; steep
East Main Street, Start at Eden St	North	Paved	3,200	N/A	planning only	\$ 1,280,000	Connect village to Gateway Commercial District
Depot Street, Start at Main St	West	Concrete	800	Good	2015	\$ 320,000	No ramp at Depot St Extension
Prospect Street, Start at Main St	North	Unknown	650	Poor	unknown	\$ 260,000	Buried by lawns, 10-feet from road shoulder
Commonwealth Ave, Start at Main St	North	Unknown	450	Poor	unknown	\$ 180,000	Buried by lawns, 10-feet from road shoulder
Johnson Street Ext, Start at Main St	East	Concrete	1,200	N/A	planning only	\$ 480,000	Possible new connection to Route 15
Route 15, Johnson St Ext to LUHS	North	Paved	2,300	N/A	planning only	\$ 920,000	Connect village to LUHS - 8' Shared Use Path
						\$ 6,488,000	

Notes -

- 1) West Main St, Main Street and Church Street would be replaced with 5' concrete sidewalks awith green strip to granite curb.
- 2) Side roads = 5' wide asphalt on new base; curb, no curb and swale to road. Need to investigate buried sidewalks on Prospect Street and Commonwealth Ave
- 3) Dufresne Engineering cost estimates used in above "Estimated Replace \$" at \$400 /ft on average - 2014 average costs - for planning purposes only